BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

## "Schedule-B"

Name of Work :- Annual Maintenance and repairs of street lights in ward no 08 Package Y -08 of Yelahanka Zone.

| Sl. No | Qty | Description Of Work | Unit | Quoted Rates | In figures |
|---|---|---|---|---|---|
| 1 | 97 | Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 36/40 W fluorescent tube light street lighting systems. | Each | 685.45 | Rupees Six Hundred Eighty Five And Paise Forty Five Only |
| 2 | 140 | Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 125 W HPMV light Park lighting systems. | Each | 756.29 | Rupees Seven Hundred Fifty Six And Paise Twenty Nine Only |
| 3 | 2030 | Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 250W HPSV street light lighting systems. | Each | 1019.41 | Rupees One Thousand Nineteen And Paise Forty One Only |
| 4 | 80 | Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents 400 watts HPSV street light/High Mast lighting systems. | Each | 1118.08 | Rupees One Thousand One Hundred Eighteen And Paise Eight Only |

For JAICAB ELECTRICALS

Proprietor

ಕಾರ್ಯ ಪಾಲಕ ಅಭಿಯಂತರರು
(ವಿದ್ಯುತ್) ಯಲಹಂಕ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

| | | | | | |
|---|---|---|---|---|---|
| 5 | 98 | Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 24 watt LED park lighting systems. | Each | 880.01 | Rupees Eight Hundred Eighty And Paise One Only |
| 6 | 27 | Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 65 watt LED street light lighting systems. | Each | 1147.43 | Rupees One Thousand One Hundred Forty Seven And Paise Forty Three Only |
| 7 | 476 | Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 90 watt LED street light lighting systems. | Each | 1377.66 | Rupees One Thousand Three Hundred Seventy Seven And Paise Sixty Six Only |
| 8 | 28 | Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 110/120 watt LED streetlight lighting system | Each | 1575.5 | Rupees One Thousand Five Hundred Seventy Five And Paise Fifty Only |
| 9 | 1 | Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 150 watt LED street light /High mast lighting system | Each | 1871.51 | Rupees One Thousand Eight Hundred Seventy One And Paise Fifty One Only |

For JAICAB ELECTRICALS

Proprietor

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
(ವಿದ್ಯುತ್) ಯಲಹಂಕ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

| | | | | | |
|---|---|---|---|---|---|
| | 110 | Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/footing of the pole.Upto 5Mtr street light pole. | Nos | 550.00 | Rupees Five Hundred Fifty Only |
| 11 | 50 | Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/footing of the pole.8Mtr and above street light pole. | Nos | 770.00 | Rupees Seven Hundred Seventy Only |
| 12 | 6 | Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.100 to 125Amps | Nos | 7200 | Rupees Seven Thousand Two Hundred Only |
| 13 | 6 | Supplying and fixing Microprocessor Based Astronomical timer Switch with using necessary bolts, nuts and washers. | Each | 4030.00 | Rupees Four Thousand Thirty Only |
| 14 | 13 | Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 50-63 Amps SP | Each | 723.00 | Rupees Seven Hundred Twenty Three Only |

I am prepared to take up the above work at rates quoted in the Schedule 'B'

For JAICAB ELECTRICALS

Contractor Proprietor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone